HASSAN DIVISION.

The 19th March 1899.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engine Hassan division, up to 10th April 1899 for restoring Ibbidi Dodakere tank, Registered No. 495, Ark gud taluk. An approximate estimate of quantities is given below. These quantities are not guarante The work should be completed by the end of June 1900.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's offic at Hassan between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executiv Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promiss Notes, as earnest money, and be superscribed "Tender for restoring Ibbidi Dodakere tank, Registe No. 495, Arkalgud taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not l himself to accept the lowest or any tender or to assign any reason whatever for the rejection of tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be requi to execute the usual contract bond ; in default of which, his tender will be considered cancelled, a his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on t notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptan or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned

Detailed abstract estimate of restoring Ibbidi Dodakere tank.

REGISTERED No. 495, ARKALGUD.

Items of work.	*Per.*	*Quantit*
Bund—		
Earthwork	C. yd.	
Cutting	C. yd.	
Turfing	Square	
Pitching with new stone work	C. yd.	
Old stone work	C. yd.	
Providing and fixing grade stones with No. bed and vis-a-vis stone	No.	
B. M. stone	No.	
Registered stone	No.	
Date stone	No.	
Gauge stone	L. S	
Execution of work at old sluice is to be blocked up	L. S.	
Sluice, left sluice—		
Earthwork excavation	C. yd.	
Surki concrete	C. ft.	4
Burnt brick in surki mortar	C. ft.	24
Burnt stone well dressed slabs	S. ft.	7
Plastering with surki mortar	Square.	2·8
Providing stone ware pipes, 6" diameter, pointing the joints with surki mortar.	R. ft.	4
Providing teak rod and plug	L. S.	
Stone work	C. yd.	
Excavating and re-filling bund	C. yd.	59
Sundry charges	L. S.	
Right sluice—		
Repairing cisterns, &c.	L. S.	
Waste weir—		
Excavating foundation	C. yd.	
Burnt brick in surki mortar	C. ft.	
Rough stone chunam	C. ft.	45
Burnt stone slabs	Sq. ft.	18
Plastering with surki mortar	Square	5·0
Rough stone work, new	C. yd.	28
Rough stone work, old	C. yd.	6
Earthen ramp	C. yd.	22
Turfing	Square	2·7
Cutting bund to extend	C. yd.	3
Sundry charges	L. S.	

A. S. NAGAVKAR, *Executive Engr.*